



Village of Southampton
71 Hill Street, Suite #1
Southampton, NY 11968
DEPARTMENT OF FIRE PREVENTION
Telephone 631 204-2152
Fax 631 283-0649
shvfiremarshal@hotmail.com

DEAN McNAMARA
Fire Marshal II
THOMAS E. SWENSON
Fire Marshal I

FIXED EXTINGUISHING SYSTEM INSTALLATION

- Application **MUST** include three (3) sets of shop drawings and three (3) set of cut sheets for all devices proposed. Drawings to be in accordance with NYS Fire and Building codes and NFPA reference standards. Shop drawings must detail the hazard to be protected and include a detailed layout and physical dimensions of all appliances and energy sources for each item to be protected by the system. Plans must be legible and clearly show the location and description of all piping and nozzles. A legend must be supplied on the drawings.
- All shop drawings **MUST** include a statement indicating “THIS INSTALLATION IS IN ACCORDANCE WITH, THE NEW YORK STATE FIRE, BUILDING CODE, NFPA 17, 17A (1998) AND MANUFACTURE’S INSTRUCTION. ONLY MANUFACTURE’S LISTED EQUIPMENT OR MANUFACTURES APPROVED ALTERNATES WILL BE USED”.
- Drawings shall be drawn to Scale.
- All shop drawings to be submitted with a signed PE STAMP FROM A LICENSED NYS ENGINEER.
- All shop drawings **MUST** state what type of system and model number that will be installed.
- Work is not to be started prior to receipt of permit/approval from the Department of Fire Prevention.
- Fixed extinguishing systems shall be tied into the fire alarm system on a separate zone, if one is already on site.
- If the system is required to be tied into a fire alarm system an alarm technician must be on site and available for trouble shooting, should a problem arise.
- Should any problems arise during the final inspection, which requires additional work or trouble shooting will possibly result in a system failure including fines, and a re-inspection scheduled for another day.
- The permit fee for an application shall include two plan reviews and a final inspection. Should the project require addition reviews and or inspections it will require a new permit fee be paid, prior to scheduling additional inspections.

Contact the Department of Fire Prevention at (631)-204-2152 at least five business days in advance to schedule an appointment for final inspection. Final inspection will include a nitrogen discharge test to verify the system is properly installed and functional. Installation shall not deviate from approved plans without prior approval in writing by the Fire Marshals Office..